



A.S. BUILDERS LLC

Commercial Construction •
Concrete • Site Work



Download
Formal PDF

Download Word
Doc (.docx)

Print
Proposal

COMMERCIAL CAPITAL EXPENDITURE PROPOSAL • REF: ASB-2026-1002-WWC

Woodway Collection Exterior Architectural Coating Refresh

Turnkey elastomeric coating application, high-durability Berridge metal awning refinishing, and comprehensive tenant continuity protocol for Regency Centers.

PROJECT ASSET

Woodway Collection

1395 S. Voss Road, Houston, TX 77057

PREPARED FOR

Ashley Blair

Property Manager • Regency Centers

PROJECT DURATION

21–24 Working Days

Target Start: Oct 19, 2026 (Weather Permitting)

TURNKEY INVESTMENT

\$128,875.00

Turnkey Sales Price (Tax: \$8,900.00)

EXECUTIVE TRANSMITTAL

Message to Regency Centers

Presented by Doug Baxley, Senior Project Manager, A.S. Builders LLC

Ashley Blair, Property Manager

Regency Centers Corporation • 3200 Kirby Drive, Suite 910,
Houston, TX 77098

Date: October 2,
2026

Status: Active
Capex Bid

Dear Ashley,

Thank you for reaching out following Kaci Hancock's recommendation, and for the opportunity to review the architectural design concepts for the **Woodway Collection** at 1395 S. Voss Road. We are excited to present this comprehensive commercial proposal for your 95% exterior property refresh.

Having served the Houston commercial sector for more than two decades, A.S. Builders understands that revitalizing an active, premier retail center in the heart of the Memorial/Tanglewood corridor requires far more than applying quality paint. It requires strict logistical discipline, immaculate site cleanliness, proactive communication, and an uncompromising commitment to ensuring your tenants—from flagship anchor **Whole Foods Market** to popular dining and boutique retail like **Buffalo Grille, Hemline, and Chico's**—experience completely seamless daily operations.

Our Core Operational Guarantee: We deploy full-time, bilingual on-site supervision and an in-house crew of seasoned commercial coating specialists. We utilize quiet off-peak scheduling, full pedestrian overhead canopy protection, and containment barriers so shoppers and diner traffic flow smoothly without interruption.

This proposal directly addresses every requirement outlined in your request, including a clear milestone schedule for Whole Foods Market review, earliest mobilization availability, and exact adherence to your Capex contracting standards. We maintain full statutory and commercial liability coverage (\$5M aggregate) and will deliver your compliant Certificate of Insurance (COI) immediately upon contract award.

We look forward to partnering with Regency Centers and bringing this beautiful new concept to life.

Doug Baxley

Senior Project Manager • A.S. Builders LLC

(832) 995-7291 • Doug@as-builders.com



DESIGN SPECIFICATIONS

The "Graphite" Color Palette System

Specified in Regency Centers' concept dated September 8, 2026

A

High Reflective White

Sherwin-Williams SW 7757

LRV: 93 • Hex: #F7F7F2

Application: Main Stucco Facades, Parapets & **ALL Walkway Soffits**

Product: SW A-100 Exterior Acrylic Latex (Standard)
/ SW Duration (Upgraded)

B

Gray Screen

Sherwin-Williams SW 7071

LRV: 59 • Hex: #C6CACA

Application: Column Bases, Lower Wainscot, Accent Pop-Outs

Product: SW A-100 / Duration Commercial Satin

C

Tricorn Black

Sherwin-Williams SW 6258

LRV: 3 • Hex: #2F2F30

Application: Parapet Coping, Cornice Line, Fascia Trims

Product: SW A-100 / Duration Semi-Gloss

D

Dark Bronze

Berridge Architectural Metal

Substrate: Metal Roof, Canopies & Steel

Application: Storefront Awnings & Whole Foods Patio Trellis

Product: SW Sher-Cryl HPA & Sher-Clear Acrylic

ALT
2

Concrete Floor Stain

H&C Colortop Solid Color

Scope: Pedestrian Slabs @ Previously Sealed Areas

Status: Optional Alternate (+\$19,000.00)

Product: H&C Colortop Water-Based Acrylic Stain

PROPERTY OVERVIEW

Woodway Collection Site Layout & Tenant Demarcations

Active retail floor plan showing anchor Whole Foods, retail wings, and excluded parcels (Carrabba's & Chase).



VISUAL SCOPE

Architectural Elevations & Scope Breakdown

Building-by-building execution plan for Woodway Collection



BUILDING 1 • NORTH-WEST RETAIL

Al's Formal • Emerson Sloan • Ella Eyes

High-profile curved eyebrow entry & pedestrian portico.

SW 7757 White Body

SW 7071 Gray Base

SW 6258 Black Coping

Dark Bronze Canopies



BUILDING 2 • SOUTH RESTAURANT DINING WING

Buffalo Grille • Shine

Active restaurant patio, high dormer gables & continuous canopies.

Off-Peak (5:00–8:30 AM)

Patio Sealed Shielding

Berridge Bronze Metal



BUILDING 3 • WEST PROMENADE

Hemline & Boutique Suites

Grand stucco archway, stepped tower parapets & side return walls.

High Stucco Parapets

Arch Header Detail

Walkway Soffits White



BUILDING 4 • CENTRAL CORRIDOR

Chico's & Inline Suites

Symmetrical parapet facade, entry columns, and wainscot banding.

Stucco Field Coating

Base Accent Gray

Continuous Black Coping



BUILDING 5 • EAST ANCHOR WING

Boardroom • Pure Barre • Bare Necessities • Vet

Multi-bay retail facade, stepped roofline, and entry porticos.

Pedestrian Walkway Prep

White Soffit Finish

Metal Awnings Refinish



BUILDING 6 • ANCHOR FLAGSHIP

Whole Foods Market Plaza & Canopy

Expansive main grocery facade, curved tower & steel patio trellis.

Covered Pedestrian Bridge

Whole Foods Logistics Plan

Zero-VOC Low-Odor

LOGISTICS & SCHEDULING

21–24 Working Day Phasing Plan

Structured to provide Whole Foods Market and retail tenants 100% operational continuity.

PHASE 1

Days 1 – 5

Mobilization & West Wing Retail

[Al's Formal Wear](#), [Emerson Sloan](#), [Ella Eyes](#), [Insideport Identessavi](#), [Hemline](#)

Site safety setup; commercial low-pressure hot bio-wash; stucco crack elastomeric routing & caulking; 100% glass masking; application of SW 7757 White body, SW 7071 Gray bases, and SW 6258 Black coping.

PHASE 2

Days 6 – 9

South Dining Wing (Special Restaurant Logistics Protocol)

[Buffalo Grille \(15\)](#) & [Pause \(16/18\)](#)

Early Morning Staging (5:00 AM – 8:30 AM): Pressure washing and spray operations completed before breakfast diners arrive. Sealed floor drops and containment tarps protect patio tables. Normal breakfast, lunch, and dinner services 100% open.

PHASE 3

Days 10 – 14

Central Promenade & East Anchor Retail Wing

[Chico's](#), [Boardroom Salon for Men](#), [Pure Barre](#), [Bare Necessities](#), [Heights Veterinary Clinic](#)

Preparation and dual-coat application across Buildings 4 & 5; complete walkway soffit coating (SW 7757 White); storefront canopy metal prep and Berridge Dark Bronze application; parking stall barrier management.

PHASE 4

Days 15 – 20

Whole Foods Market Anchor Flagship Centerpiece

[Whole Foods Main Storefront](#), [Curved Tower](#), [Architectural Steel Pergola & Trellis](#)

Whole Foods Compliance: Installation of heavy-duty covered pedestrian bridge/scaffolding over primary grocery entrance doors. Articulated boom lift operations staged off-peak. Low-VOC formulations prevent scent intrusion into produce sections. Grocery delivery loading docks 100% unimpeded.

PHASE 5

Days 21 – 24

Architectural Detailing, Punch Walk & Demobilization

[Regency Centers Property Walk with Ashley Blair](#)

Comprehensive detail cut-in inspections; removal of all masking tape and protective floor paper; glass cleaning of storefront windows; joint property walk-through with Ashley Blair for final punch list sign-off.

CAPEX COMMERCIAL INVESTMENT

Itemized Cost Schedule

Turnkey proposal lump-sum formatted for Regency Centers' Capital Expenditure Contract.

ITEM #	SCOPE ITEM & SPECIFICATIONS	AREA / COVERAGE	AMOUNT
1.0	Site Mobilization, Bio-Wash Prep, Crack Repair & Joint Caulking Center-wide hot-water wash (2,500 PSI), bio-fungicide treatment, elastomeric caulking.	Full 95% Project Boundary	\$16,500.00
2.0	West & North Retail Wing Facades & Soffits Stucco body (SW A-100 White), accent bases (SW Gray Screen), coping (SW Black).	Buffalo Grille, Nails of America, Paris Texas, Framebridge	\$26,800.00
3.0	Central Inline & East Retail Wing Promenade facades, wainscot banding, white pedestrian soffits, black parapet caps.	Boardroom Salon, Pure Barre, Bluemercury, Nothing Bundt Cakes	\$24,600.00
4.0	Whole Foods Market Anchor Facade (Bldg 6) High-reach main grocery parapet, curved tower, and covered pedestrian portal tunnel.	Whole Foods Market Main Storefront	\$32,400.00
5.0	Architectural Metal Roof, Canopies, Gutters & Plaza Trellis Sherwin-Williams Sher-Cryl HPA & Sher-Clear acrylic coating (Berridge Dark Bronze finish).	Metal Roof, Storefront Canopies & Steel Trellis	\$16,750.00
6.0	Heavy Equipment, Articulated Boom Lifts & Pedestrian Protection 45ft/60ft boom lifts, safety barricades, covered pedestrian bridge infrastructure.	Project Duration Infrastructure	\$11,825.00

ITEM #	SCOPE ITEM & SPECIFICATIONS	AREA / COVERAGE	AMOUNT
Total Standard Commercial Value:			\$148,875.00
Regency Centers Preferred Client & Combined Mobilization Credit:			-\$20,000.00
BASE COMMERCIAL PROPOSAL SALES PRICE (LUMP-SUM):			\$128,875.00
Sales Tax (If Applicable / Required by Regency Centers):			\$8,900.00
TOTAL TURNKEY BASE PROPOSAL WITH SALES TAX:			\$137,775.00
ALT 1	ALT. ADD: TO USE DURATION PAINT Upgrade all exterior walls, parapets, and stucco elevations center-wide to Sherwin-Williams Duration Exterior Acrylic Coating.	Full Center Elevations	+\$9,700.00
ALT 2	ALT. ADD: STAIN CONCRETE FLOORS @ PREVIOUSLY SEALED AREA Commercial mechanical cleaning, acid/neutralization prep, and dual-coat application of H&C Colortop Water-Based Solid Color Concrete Stain.	Pedestrian Walkways	+\$19,000.00

Capex Schedule & Optional Alternates

- **20% (\$25,775.00)** • Mobilization & Materials
- **40% (\$51,550.00)** • Substantial Completion Retail Wings Bldgs 1–5
- **30% (\$38,662.50)** • Whole Foods & Metal Roof/Canopies
- **10% (\$12,887.50)** • Final Retainage upon Sign-Off

Project Alternates:

- **ALT. ADD: \$9,700.00** – TO USE DURATION PAINT

VersaPay Integration & Insurance

A.S. Builders is fully integrated into **VersaPay** on **Net 30** terms. We carry \$5,000,000 commercial umbrella/liability and statutory workers' compensation, with Regency Centers Corporation designated as Additional Insured.

• **ALT. ADD: \$19,000.00** – STAIN CONCRETE
FLOORS @ PREVIOUSLY SEALED AREA

A.S. Builders LLC • Commercial Construction & Site Services

12040 E. Hardy Rd., Houston, TX 77039 • Direct: (832) 995-7291 • Office: (713) 377-2111

Doug@as-builders.com • www.as-builders.com

"Built on Safety, Delivered with Quality"